



Advance Bill of Material

Project Number: XX183

Building: Clinker Silo Dome & Preheater

Date: 19.12.2023

SNo.	SIZE	MATERIAL	LENGTH (mm)	WEIGHT (kg)	REMARKS
1	ISMB500	IS2062	31,392.00	2,735.30	Clinker Silo Dome
2	ISMC75	IS2062	54,41,161.50	38,868.90	Clinker Silo Dome
3	ISMC100	IS2062	14,76,915.10	14,144.40	Clinker Silo Dome
4	ISMC125	IS2062	2,70,378.30	3,544.50	Clinker Silo Dome
5	ISMC150	IS2062	4,26,607.00	7,133.10	Clinker Silo Dome
6	ISMC200	IS2062	19,42,988.50	43,469.50	Clinker Silo Dome
7	ISMC300	IS2062	1,66,501.50	6,051.60	Clinker Silo Dome
8	ROD12	IS2062	9,81,751.60	784.70	Clinker Silo Dome
9	ISA50X50X6	IS2062	426311.2	1900.8	Preheater
10	ISA65X65X6	IS2062	945484.1	5522.0	Preheater
11	ISA75X50X6	IS2062	595.0	3.3	Preheater
12	ISA75X75X6	IS2062	337413.3	2293.8	Preheater
13	ISA75X75X8	IS2062	22427.5	200.7	Preheater
14	ISA90X90X6	IS2062	30303.9	249.8	Preheater
15	ISA90X90X8	IS2062	27034.1	292.9	Preheater
16	ISA150X90X12	IS2062	1760.0	38.0	Preheater
17	ISMB200	IS2062	66393.1	1605.3	Preheater
18	ISMB250	IS2062	64482.3	2404.4	Preheater
19	ISMB300	IS2062	152744.7	7026.4	Preheater
20	ISMB400	IS2062	55666.3	3425.9	Preheater
21	ISMB450	IS2062	12469.8	902.5	Preheater
22	ISMB500	IS2062	67287.3	5863.1	Preheater
23	ISMB600	IS2062	60394.2	7395.9	Preheater
24	ISMC75	IS2062	42198.0	301.4	Preheater
25	ISMC100	IS2062	203689.8	1950.7	Preheater
26	ISMC125	IS2062	150902.2	1978.3	Preheater
27	ISMC150	IS2062	7310.0	122.2	Preheater
28	ISMC200	IS2062	359414.0	8041.0	Preheater
29	ISMC250	IS2062	143910.6	4405.8	Preheater
30	ISMC300	IS2062	4244.6	154.3	Preheater
31	ISMC400	IS2062	33434.0	1674.5	Preheater
Total				1,74,485.0	